

Material's list for Framing, Drywall and Insulation. Totals for the entire project.

FRAMING / MATERIAL LIST			
2 X 4 WALLS	18 GAUGE METAL FRAMED WALLS		32,756 LN FT
	18 GA 3 5/8" studs @16" OC	319,371	LN FT
	18 GA 3 5/8" studs, double stud at openings	71,280	LN FT
	18 GA 3 5/8" top & bottom tracks	78,614	LN FT
	Caulkin, non drying at bottom tracks	36,031	LN FT
	Simpson shot pin PHN-32 1 1/4" @16" OC	27,024	EA
	# 10 Screws	765	LB
2 X 6 WALLS	18 GAUGE METAL FRAMED WALLS		22,142 LN FT
	18 GA 6" studs @ 16" OC	215,885	LN FT
	18 GA 6" studs, double stud at openings	20,852	LN FT
	18 GA 6" top & bottom tracks	53,140	LN FT
	Caulkin, non drying at bottom tracks	24,356	LN FT
	Simpson shot pin PHN-32 1 1/4" @16" OC	16,606	EA
	# 10 Screws	517	LB
2 X 8 WALLS	18 GAUGE METAL FRAMED WALLS		1,687 LN FT
	18 GA 8" studs @ 16" OC	13,920	LN FT
	18 GA 8" studs, double stud at openings	3,615	LN FT
	18 GA 8" top & bottom tracks	3,725	LN FT
	Caulkin, non drying at bottom tracks	1,856	LN FT
	Simpson shot pin PHN-32 1 1/4" @16" OC	1,392	EA
	# 10 Screws	40	LB
2 X 8 CLINGS	20 GAUGE METAL FRAMED FURRED CEILINGS		171,831 SQ FT
	20 GA 8" studs @ 16" OC	164,957	LN FT
	Resilient channels @ 24" OC	103,099	LN FT
	18 GA 8" tracks	88,436	LN FT
	Simpson shot pin PHN-32 1 1/4" @16" OC	65,327	EA
	# 10 Screws	502	LB
2 X 4 CLINGS	20 GAUGE METAL FRAMED CEILINGS AND SOFFITS		60,207 SQ FT
	20 GA 3 5/8" studs @ 16" OC	57,799	LN FT
	Resilient channels @ 24" OC	36,124	EA
	18 GA 3 5/8" tracks	7,448	LN FT
	Simpson shot pin PHN-32 1 1/4" @16" OC	32,556	EA
	# 10 Screws	176	LB

ROOF	16 & 18 GAUGE FRAMING ROOF, STAIR'S SHAFT ROOF (SLOPED)	6,137	SQ FT
	4" 16 GA HDS beams w/ 16 GA 6" track	1032	LN FT
	6" 16 GA double studs beam w/ 16 GA 6" track	1108	LN FT
	6" 18 GA ceiling joists @ 16 " OC	4620	LN FT
	6" 18 GA Double king post	148	LN FT
	Simpson LS 50 @ 48"OC	346	EA
	HSS 4 X 4 X 1/4 King post	98	LN FT
	18 GA Brake shape track	1207	LN FT
	# 10 Screws	20	LB
ROOF	16 & 18 GAUGE FRAMING ROOF, ELEVATOR'S SHAFT ROOF (FLAT)	1,385	SQ FT
	4" 16 GA HDS beams w/ 16 GA 6" track	80	LN FT
	6" 14 GA Rim Track	564	LN FT
	6" 18 GA ceiling joists @ 16 " OC	1360	LN FT
	# 10 Screws	3	LB
ROOF	16 & 18 GAUGE FRAMING ROOF, BUILDING ROOF OVER CONCRETE ROOF (SLOPED)	20,207	SQ FT
	6" 14 GA HDS beams w/ 16 GA 6" track	1299	LN FT
	6" 18 GA ceiling joists @ 16 " OC	16364	LN FT
	6" 18 GA Double king post	158	LN FT
	Simpson S/H 2.5 @ 48"OC	1970	EA
	16 GA Brake shape track	2084	LN FT
	# 10 Screws	65	LB
HOME STAIRS	STAIRS WOOD FRAMED, 3'-6" WIDE STEPS, 7" RISERS (1,652 STEPS)	5,782	LN FT
	2 x 14 Stair stringers	3,505	LN FT
	2 x 4 Spacer	3,450	LN FT
	2 x 4 PTDF plate anchor	676	LN FT
	2 x 8 Joist	2,331	LN FT
	1 1/8" Plywood sub floor	13,200	SQ FT
	16d Nails	1,210	LB

DRYWALL / MATERIAL LIST

DRYWALL	ALL AREAS	1,132,986	SQ FT
	5/8" gypsum wallboard, 4' x 10'	588,500	SQ FT
	5/8" gypsum wallboard, 4' x 8'	289,857	SQ FT
	5/8" Type X gypsum wallboard 4' x 10'	112,992	SQ FT
	5/8" gypsum wallboard, exterior grade 4' x 10'	97,071	SQ FT
	1/2" Dens shield Tile Backer, 4' x 8'	24,345	SQ FT
	APA 15/32" Plywood, 4' x 8'	20,221	SQ FT
	1 1/4" galvanized corner bead	52,356	LN FT
	Tape	1,700	EA 500' ROLL
	Joint compound	9,764	GAL
	Thin skim coat	3,600	GAL
	Type S screws	6,987	LB

INSULATION / MATERIAL LIST

INSULATION	ALL AREAS	769,137	SQ FT
------------	-----------	---------	-------

R-15 Walls Insulation	590,808	SQ FT
R-30 Ceiling Insulation	255,240	SQ FT