

THE NEW YORKER - LOS FELIZ / Six-Tract, Three- Story Single Family Dwellings
1657 New Hampshire Ave, Los Angeles CA 90027

ALL BUILDINGS (LOT 1 THRU LOT 6)

DRYWALL

WALL DRYWALL		GRAND TOTAL	
6" PROPERTY LINE GAP / DENSGLASS	Building to building property exterior walls , 5/8" DensGlass over paper	4,976	SQ FT
BROWN BOARD BEHIND METAL SIDING	Metal siding exterior walls, 5/8" brown board backing	4,269	SQ FT
GARAGE WALLS / 1 HR	Garage inside walls, 5/8" Type X drywall	3,284	SQ FT
PERIMETER WALLS / 1HR	Perimeter inside walls, 5/8" Type X drywall	16,634	SQ FT
INTERIOR WALLS	Interior walls, 5/8" Type X drywall	17,333	SQ FT
PLUMBING CHASE	Second level plumbing chase walls, 5/8" Type X drywall	450	SQ FT
TILE BACKER BOARD	Tile backer board at interior tile locations, 5/8" DensShield board	1,708	SQ FT
Sub Total Drywall Walls		48,654	SQ FT

CEILING DRYWALL		GRAND TOTAL	
BROWN BOARD BEHIND METAL SIDING	Metal siding exterior ceilings, 5/8" brown board backing	467	SQ FT
GARAGE CEILING / 1 HR	Garage ceiling, 5/8" Type X drywall	2,067	SQ FT

SOFFITS	Soffits, 5/8" Type X drywall	1,978	SQ FT
CEILINGS	First and second levels ceiling, 5/8" Type X drywall	3,799	SQ FT
CEILINGS	Third level and roof deck level ceilings, 5/8" drywall	3,344	SQ FT
STAIRS CEILINGS	Ceiling under stairs, 5/8" Type X drywall	1,014	SQ FT

Sub Total Drywall Ceilings		12,669	SQ FT
-----------------------------------	--	---------------	--------------

TOTAL DRYWALL		61,323	SQ FT
----------------------	--	---------------	--------------

" J " MOLD AT DOORS AND WINDOWS		GRAND TOTAL	
DOOR FRAMES "J" MOLDING	" J " Molding at all door openings	3,144	LN FT
WINDOW FRAMES "J" MOLDING	" J " Molding at all window openings	1,342	LN FT

TOTAL "J" MOLDING		4,486	LN FT
--------------------------	--	--------------	--------------